



ADDENDUM 1 OF 1

SOLICITATION NUMBER: 2024 RFP ENG-122G
SOLICITATION TITLE: GENTILLY ROAD SIDEWALK
DUE DATE: WEDNESDAY, MAY 8, 2024 AT 3:00 PM

THIS DOCUMENTATION MUST BE INCLUDED IN YOUR SUBMITTED SEALED BID FOR THE BID TO BE CONSIDERED.

- Question 1. What is the material of the waterlines?
Answer The lines in the area are older so it will be a mixture of either Galvanized or Copper. Contractors should visit the site to verify materials needed to accurately determine their bids.
- Question 2. Will we have to tap in live or is there a way to shut off the service at the main for the area?
Answer If you can tie into the line to relocate the meter after the curb stop then yes otherwise it'll have to be done live.
- Question 3. Revised Bid tab to reflect the water meter relocation, street sign removal / relocation, and the flared end section unit type?
Answer Please see attached for revised bid tab.

RECEIPT OF ADDENDUM 1 OF 1 ACKNOWLEDGED: SIGNATURE: _____



Bid- Table

City of Statesboro

ENG-122g : Gentilly Sidewalk from E. Jones Ave -- Savannah Ave.

General Conditions

Pay Item #	Item Description	Qty.	Unit	Unit Price	Total
1	Traffic Control	1	LS		
2	Mobilization	1	LS		
3	Grading Complete (include all clearing / tree removal and demo work)	1	LS		

Erosion and Sedimentation Control

Pay Item #	Item Description	Qty.	Unit	Unit Price	Total
4	Temporary Grassing	1	Acre		
5	Mulch	10	TN		
6	Inlet Sediment Trap (install & remove)	7	EA		
7	Type-C Silt Fence (install & remove)	1900	LF		
8	Permanent Grassing	1	Acre		

Roadway & Drainage

Pay Item #	Item Description	Qty.	Unit	Unit Price	Total
9	Foundation Backfill Matl, Tp II (pipe bedding)	25	CY		
10	Gr Aggr Base Course, 6 inch, Incl Matl	45	TN		
11	Concrete Valley Gutter, 6 in. (Driveway Concrete)	200	SY		
12	Concrete Sidewalk, 4 in	1200	SY		
13	Concrete Curb & Gutter, 6in x 30 in	250	LF		
14	Storm Drain Pipe, 18in, H 1-10, RCP	16	LF		
15	Sidewalk Safety Handrails	40	LF		
16	18" RCP Flared End Section	1	EA		
17	ADA Ramp Installation	6	EA		
18	Water Meter Relocation	12	EA		
19	Plastic Filter Fabric, Woven 200-lb Tensile All Directions	3	SY		

Signing and Striping

Pay Item #	Item Description	Qty.	Unit	Unit Price	Total
20	Thermoplastic Solid Traf Stripe, 5 in, White Crosswalks	62	SY		
21	W 11-2 (30"x30")	37.5	SF		
22	W16-7P (12"x24")	8	SF		
23	W16-9P (12"x24")	4	SF		
24	R1-6A (12"x36")	6	SF		
25	Square Tube Post Type 7	30	LF		
26	Remove / Relocate Structures (street signs)	1	LS		

Materials As Directed by Engineer

Pay Item #	Item Description	Qty.	Unit	Unit Price	Total
MA-9	Foundation Backfill Matl, Tp II (pipe bedding)	10	CY		
MA-10	Gr Aggr Base Course, 6 inch, Incl Matl	45	TN		
MA-11	Concrete Valley Gutter, 6 in. (Driveway Concrete)	20	SY		
MA-12	Concrete Sidewalk, 4 in	120	SY		
MA-13	Concrete Curb & Gutter, 6in x 30 in	25	LF		

Total Base Bid: _____